


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input type="checkbox"/>				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Gilbert 14-32-2-3W				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT UNDESIGNATED				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Patented			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Newfield RMI LLC						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-823-1932				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 1001 17th Street, Suite 2000, Denver, CO 80202						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		934 FSL 1913 FWL		SESW	32	2.0 S	3.0 W	U		
Top of Uppermost Producing Zone		934 FSL 1913 FWL		SESW	32	2.0 S	3.0 W	U		
At Total Depth		934 FSL 1913 FWL		SESW	32	2.0 S	3.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 934			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1584			26. PROPOSED DEPTH MD: 11600 TVD: 11600				
27. ELEVATION - GROUND LEVEL 5736			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Cond	17.5	14	0 - 60	37.0	H-40 ST&C	0.0	Hi Lift "G"	35	1.17	15.8
Surf	12.25	9.625	0 - 2200	36.0	J-55 LT&C	8.3	Premium Lite High Strength	51	3.53	11.0
							Hi Lift "G"	523	1.17	15.8
I1	8.75	7	0 - 9400	26.0	P-110 LT&C	9.5	35/65 Poz	260	3.53	12.0
							50/50 Poz	253	1.29	14.0
Prod	6.125	4.5	9200 - 11600	11.6	P-110 LT&C	11.5	50/50 Poz	113	2.31	14.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent			PHONE 435 719-2018			
SIGNATURE				DATE 01/30/2013			EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43013519980000				APPROVAL  Permit Manager						

Newfield Production Company
14-32-2-3W
SE/SW Section 32, T2S, R3W
Duchesne County, UT

Drilling Program

1. Formation Tops

Uinta	surface
Green River	4,570'
Garden Gulch member	7,510'
Wasatch	10,060'
TD	11,600'

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	1,954'	(water)
Green River	7,510' - 10,060'	(oil)
Wasatch	10,060' - TD	(oil)

3. Pressure Control

Section BOP Description

Surface 12-1/4" diverter

Interm/Prod The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Coup	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom							Burst	Collapse	Tension
Conductor	0'	60'	37	H-40	Weld	--	--	--	--	--	--
14									--	--	--
Surface	0'	2,200'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
9 5/8									2.85	2.89	5.72
Intermediate	0'	9,400'	26	P-110	LTC	9	9.5	15	9,960	6,210	693,000
7									2.24	1.68	2.84
Production	9,200'	11,600'	11.6	P-110	LTC	11	11.5	--	10,690	7,560	279,000
4 1/2									1.95	1.31	2.07

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	500'	Premium Lite II w/ 3% KCl + 10% bentonite	180	15%	11.0	3.53
				51			
Surface Tail	12 1/4	1,700'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	612	15%	15.8	1.17
				523			
Intermediate Lead	8 3/4	5,310'	HLC Premium - 65% Class G / 35% Poz + 10% Bentonite	918	15%	12.0	3.53
				260			
Intermediate Tail	8 3/4	1,890'	50/50 Poz/Class G + 1% bentonite	327	15%	14.0	1.29
				253			
Production Tail	6 1/8	2,400'	50/50 Poz/Class G + 1% bentonite	260	15%	14.0	2.31
				113			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate and production casing strings will be calculated from an open hole caliper log, plus 15% excess.

6. Type and Characteristics of Proposed Circulating Medium

Interval

Description

Surface - 2,200'

An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.

2,200' - TD

One of two possible mud systems may be used depending on offset well performance on ongoing wells: A
water based mud: Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will

be weighted with additions of bentonite, and if conditions warrant, with barite.

-or-

A diesel based OBM system: with an oil to water ratio between 70/30 and 80/20. Emulsifiers and wetting agents will be used to maintain adequate mud properties. A water phase salinity will be maintained in the range of 25% using CaCl (Calcium Chloride).

Anticipated maximum mud weight is 11.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run from TD to the base of the surface casing. A compensated neutron/formation density log will be run from TD to the top of the Garden Gulch formation. A cement bond log will be run from PBTD to the cement top behind the production casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.57 psi/ft gradient.

$$11,600' \times 0.57 \text{ psi/ft} = 6635 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

This is planned as a vertical well.

Newfield requests the following variances from Onshore Order #2:

- Variance from Onshore Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0


If oil based mud (OBM) is used, all processed OBM drill cuttings would be removed from the well bore using a closed loop system. OBM cuttings would be dried and centrifuged and then temporarily stored within a lined pit that would be constructed inboard of the pad area. The pit would be lined with 16 mil (minimum) thickness polyethylene nylon reinforced liner material. The liner(s) would overlay straw, dirt and/or bentonite if rock is encountered during excavation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit, and a minimum of two feet of free board would be maintained between the maximum fluid level and the top of the pit at all times. All OBM cuttings will be mechanically dried and centrifuged so that they can be easily transferred to a lined cuttings pit with little to no free fluid on them. Samples of the mechanically dried OBM cuttings will be taken for chemical analysis. The OBM cuttings will then be mixed with a chemical drying agent and the chemically dried OBM cuttings will be placed in a lined cuttings pit on the generating location that is separated from the water based cuttings. The pit

will be of sufficient size to contain all cuttings generated in the drilling process. At this point, the chemically dried OBM cuttings are ready for the Firmus® construction process or the OBM cuttings may also be transported to a state approved disposal facility. If an oil based mud is not used, a conventional reserve pit will be utilized. The pit will be reclaimed using UDOGM and BLM approved procedures.

CONFIDENTIAL

T2S, R3W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**

5301.12' (G.L.O.)




= SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

NAD 83 (SURFACE LOCATION)
LATITUDE = 40°15'37.80"
LONGITUDE = 110°14'59.13"
NAD 27 (SURFACE LOCATION)
LATITUDE = 40°15'37.96"
LONGITUDE = 110°14'56.57"


WELL LOCATION, 14-32-2-3W, LOCATED AS SHOWN IN THE SE 1/4 SW 1/4 OF SECTION 32, T2S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 04-25-12	SURVEYED BY: M.C.	VERSION:
DATE DRAWN: 05-02-12	DRAWN BY: R.B.T.	V2
REVISED: 01-15-13 V.H.	SCALE: 1" = 1000'	

RECEIVED: January 30, 2013

Access Road Map



Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-32-2-3W
SEC. 32, T2S, R3W, U.S.B.&M.
Duchesne County, UT.


DRAWN BY:	A.P.C.	REVISED:	01-15-13 D.C.R.	VERSION:
DATE:	05-16-2012			V2
SCALE:	1:100,000			

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-32-2-3W
SEC. 32, T2S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY: A.P.C. REVISED: 01-15-13 D.C.R. VERSION:

DATE: 05-16-2012


SCALE: 1" = 2,000'

V2

TOPOGRAPHIC MAP

SHEET

B



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



P: (435) 781-2501
F: (435) 781-2518




NEWFIELD EXPLORATION COMPANY

14-32-2-3W
SEC. 32, T2S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	01-15-13 D.C.R.	VERSION:
DATE:	05-16-2012			V2
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET
C1

Proposed Pipeline Map

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518


**NEWFIELD EXPLORATION COMPANY**

14-32-2-3W
SEC. 32, T2S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	01-15-13 D.C.R.	VERSION:
DATE:	05-16-2012			V2
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET
C2



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-32-2-3W
SEC. 32, T2S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY: A.P.C. REVISED: 01-15-13 D.C.R. VERSION:

DATE: 05-16-2012

SCALE: 1" = 2,000'

V2

TOPOGRAPHIC MAP

SHEET

D

AFFIDAVIT OF SURFACE OWNERSHIP AND SURFACE USE

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Landman for Newfield RMI LLC ("Newfield RMI"), whose address is 1001 17th Street, Suite 2000, Denver, CO 80202.
2. Newfield Production Company ("Newfield") is the Operator of the proposed Gilbert 14-32-2-3W well with a surface location to be positioned in the SESW of Section 32, Township 2 South, Range 3 West, Duchesne County, Utah (the "Drillsite Location").
3. Pursuant to that certain Special Warranty Deed dated June 20, 2012 from Alpine Partners, a Utah General Partnership, to Newfield RMI, recorded in Book A649, Page 533, and Document # 446789 of the official records of Duchesne County, Utah, Newfield RMI is the surface owner of the Drillsite Location.
4. Newfield has the right to construct and operate the Gilbert 14-32-2-3W Drillsite Location.

FURTHER AFFIANT SAYETH NOT.



Peter Burns

ACKNOWLEDGEMENT

STATE OF COLORADO §
CITY AND §
COUNTY OF DENVER §


Before me, a Notary Public, in and for the State, on this 22nd day of January, 2013, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.


NOTARY PUBLIC


My Commission Expires:




Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD EXPLORATION COMPANY**PROPOSED LOCATION LAYOUT****14-32-2-3W***Pad Location: SESW Section 32, T2S, R3W, U.S.B.&M.*

NOTE:

The topsoil & excess material areas are calculated as being mounds containing 4,560 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.

SURVEYED BY: M.C.	DATE SURVEYED: 04-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 05-02-12	V2
SCALE: 1" = 60'	REVISED: V.H. 01-15-13	

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078





RECEIVED: January 30, 2013

NEWFIELD EXPLORATION COMPANY

CROSS SECTIONS

14-32-2-3W

Pad Location: SESW Section 32, T2S, R3W, U.S.B.&M.



NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1


ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	15,450	15,450	Topsoil is not included in Pad Cut Volume	0
PIT	1,420	0		1,420
TOTALS	16,870	15,450	2,730	1,420

SURVEYED BY: M.C.	DATE SURVEYED: 04-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 05-02-12	V2
SCALE: 1" = 60'	REVISED: V.H. 01-15-13	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 30, 2013


NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****14-32-2-3W***Pad Location: SESW Section 32, T2S, R3W, U.S.B.&M.*

SURVEYED BY: M.C.	DATE SURVEYED: 04-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 05-02-12	V2
SCALE: 1" = 60'	REVISED: V.H. 01-15-13	



Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 30, 2013

CONFIDENTIAL



API Number: 4301351998
Well Name: Gilbert 14-32-2-3W
Township T02.0S Range R03.0W Section 32
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
 Map Prepared:
 Map Produced by Diana Mason



Well Name	NEWFIELD PRODUCTION COMPANY Gilbert 14-32-2-3W 430135199			
String	Cond	Surf	I1	Prod
Casing Size(")	14.000	9.625	7.000	4.500
Setting Depth (TVD)	60	2200	9400	11600
Previous Shoe Setting Depth (TVD)	0	60	2200	9400
Max Mud Weight (ppg)	8.3	8.3	9.5	11.5
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1000	3520	9950	10690
Operators Max Anticipated Pressure (psi)	6635			11.0

Calculations	Cond String	14.000	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient

Calculations	Surf String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	950	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	686	NO diverter
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	466	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	479	NO No expected pressure
Required Casing/BOPE Test Pressure=		2200	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	4644	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3516	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2576	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3060	NO OK
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2200	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	6937	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	5545	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4385	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	6453	YES
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		9400	psi *Assumes 1psi/ft frac gradient

43013519980000 Gilbert 14-32-2-3W

Casing Schematic

Surface

9-5/8"
MW 8.3
Frac 19.3

7"
MW 9.5
Frac 19.3

4-1/2"
MW 11.5

14" I Conductor Uinta
60'

to 0' @ 3% w/o, tail 526'
TOC @ 828.

*St. C ✓

2100' ± BMSW
Surface
2200, MD

to 2321' @ 3% w/o, tail 7543'
* Proposed to 2200'

TOC @ 4570' Green River
4551.

*SP.P ✓

7510' Garden Gulch mbr.

8128' tail

12%
TOL @ 9200.

Intermediate
9400, MD

to TOL @ 3% w/o

TOC @ 10060' Wasatch
9815.

Production Liner
11600, MD

CONFIDENTIAL

Stop cuts.

Well name:	43013519980000 Gilbert 14-32-2-3W		
Operator:	NEWFIELD PRODUCTION COMPANY		
String type:	Surface	Project ID:	43-013-51998
Location:	DUCHESNE COUNTY		

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 105 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 828 ft

Burst

Max anticipated surface pressure: 1,936 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,200 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 1,929 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 9,400 ft
Next mud weight: 9.500 ppg
Next setting BHP: 4,639 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,200 ft
Injection pressure: 2,200 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2200	9.625	36.00	J-55	LT&C	2200	2200	8.796	17990
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	952	2020	2.122	2200	3520	1.60	79.2	453	5.72 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: March 18, 2013
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2200 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013519980000 Gilbert 14-32-2-3W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Intermediate	Project ID: 43-013-51998
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 9.500 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 206 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 4,551 ft

Burst

Max anticipated surface pressure: 4,378 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,446 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 8,053 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 11,600 ft
Next mud weight: 11.500 ppg
Next setting BHP: 6,930 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 9,400 ft
Injection pressure: 9,400 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9400	7	26.00	P-110	LT&C	9400	9400	6.151	97713
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4639	6230	1.343	6446	9950	1.54	244.4	693	2.84 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: March 18, 2013
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9400 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013519980000 Gilbert 14-32-2-3W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production Liner	Project ID: 43-013-51998
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 11.500 ppg
Internal fluid density: 1.000 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 236 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Burst:

Design factor 1.00

Cement top: 9,815 ft

Burst

Max anticipated surface pressure: 4,378 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,930 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Liner top: 9,200 ft

Non-directional string.

Tension is based on air weight.

Neutral point: 11,187 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2400	4.5	11.60	P-110	LT&C	11600	11600	3.875	11563
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	6327	7580	1.198	6930	10690	1.54	27.8	279	10.02 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: March 18, 2013
Salt Lake City, Utah

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 11600 ft, a mud weight of 11.5 ppg. An Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Gilbert 14-32-2-3W
API Number 43013519980000 **APD No** 7554 **Field/Unit** UNDESIGNATED
Location: **SESW** **Sec** 32 **Tw** 2.0S **Rng** 3.0W 934 **FSL** 1913 **FWL**
1/4, 1/4
GPS Coord (UTM) 563798 4456941 **Surface Owner** Newfield RMI LLC

Participants

Corie Miller - Newfield

Regional/Local Setting & Topography

This location is situated 3.5 miles Southwest of the town of Upalco and Sand Wash Reservoir on the northern most portion of the Blue Bench. The soils are silty sands with some exposed gypsum and rounded clastic gravels. The surrounding lands are highly eroded and quite steep slopes to flood plain below which leads directly to the Lake Fork River. The location is proposed over two deeply incised erosional features and disturbance will exceed the boundaries of each as well as they encroach the very edge of the steep and tall bench with up to 20 feet of fill. The most deeply eroded of these drainages supports juniper tress and riparian vegetation. The reserve pit is planned on top of this feature. The surface is moderately barren of vegetation besides Mat Atriplex and Galleta. Utah Juniper encircle the location regionally and generally only along the rims of the bench. No wildlife or cultural resources were noted during the visit. The area has not been previously disturbed or used for grazing, agriculture or industrial purposes though future development for petroleum extraction is planned and has been permitted for the near future. The Lake Fork River, Zimmerman Wash, and Uteland & Redcap Canals are found within a one mile radius. This is also within the Sage Grouse polygon.

Surface Use Plan

Current Surface Use
 Wildlfe Habitat

New Road Miles	Well Pad	Src Const Material	Surface Formation
1.8	Width 300 Length 400	Onsite	UNTA

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands Y
 but is above and immediately adjacent such feature

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;
site covered in deep snow.

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits, though none were observed.

Within the Sage Grouse critical habitat polygon. DWR had no issues

Soil Type and Characteristics

expected soils are silty sands with clastic gravels and gypsum stones

Erosion Issues Y

Sedimentation Issues Y

Site Stability Issues Y

Drainage Diversion Required? Y

Berm Required? Y

Erosion Sedimentation Control Required? Y

anything leaving location will immediately enter floodplain / riparian below

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	75 to 100	10
Distance to Surface Water (feet)		20
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	>1320	0
Native Soil Type	Mod permeability	10
Fluid Type	Oil Base Mud Fluid	15
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	10 to 20	5
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		60 1 Sensitivity Level

Characteristics / Requirements

Plans show a reserve pit on top of an existing drainage although, Operator is expected to use a closed loop system and oil based drilling fluids. I think closed loop is appropriate for this location.

Closed Loop Mud Required? Y Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

This location is planned to exceed the edge of the bench and fill slopes will extend down the slopes. The floodplain below leads directly to the Lake fork River.

I think the location should at a minimum be moved north away from the edge, corners rounded and reserve pit (if used) moved north as well out of the drainage. Closed loop is appropriate here. As this is a Horizontal well it is already outside the drilling window.

Chris Jensen
Evaluator

2/27/2013
Date / Time

CONFIDENTIAL

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner CBM
7554	43013519980000	LOCKED	OW	P No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Newfield RMI LLC
Well Name	Gilbert 14-32-2-3W		Unit	
Field	UNDESIGNATED		Type of Work	DRILL
Location	SESW 32 2S 3W U 934 FSL 1913 FWL GPS Coord (UTM) 563800E 4456935N			

Geologic Statement of Basis

Newfield proposes to set 60' of conductor and 2,200' of surface casing at this location. An air and/or fresh water mud system will be used for drilling the surface hole. The base of the moderately saline water at this location is estimated to be at a depth of 2,100'. A search of Division of Water Rights records shows 14 water wells within a 10,000 foot radius of the center of Section 32. The wells are privately owned. Depth is listed as ranging from 30-910 feet. Water use is listed as irrigation, stock watering, and domestic use. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

3/14/2013
Date / Time

Surface Statement of Basis

Location is proposed in a suspect location outside the spacing window exceeding the edge of the bench. Access road enters the pad from the West. The Operator is, in this case, the landowner and its representative was in attendance for the pre-site inspection.

The soil type and topography at present do combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions. Fluids leaving the pad will have a direct route to the floodplain / riparian below.

Usual construction standards of the Operator do not appear to be adequate for the proposed purpose as submitted. Plans lack measures for protection of slopes. Corner A of the reserve pit is planned in fill. For this reason I have asked for a closed loop system and operator has expressed the likelihood of oil based drilling fluids .

I quickly recognize no special flora or animal species or cultural resources on site that the proposed action may harm but, location is within critical habitat for Greater Sage Grouse. A deep drainage with Juniper and/ or riparian vegetation can be found within location boundaries on the West. The location was not previously surveyed for cultural, animal or paleontological resources as the operator saw fit. I have advised the operator take all measures necessary to comply with ESA and MBTA and that actions insure no disturbance to species that may have not been seen during onsite visit.

The location should be bermed to prevent fluids from entering or leaving the confines of the pad. Fencing around the reserve pit will be necessary to prevent wildlife and livestock from entering. A synthetic liner of 16 mils (minimum) with felt subliner should be utilized in the reserve pit if permitted. Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues to include significantly

rounding corners 2 and 8. Care to be taken that overland flows do not impact or erode topsoil pile near bench edge adjacent corner 2 or topsoils will need to be stored elsewhere onsite. Plans to be resubmitted as a sundry reflecting these changes

Chris Jensen
Onsite Evaluator

2/27/2013
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A closed loop mud circulation system is required for this location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location. Buried drainages need to be compacted and stabilized.
Surface	Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues to include significantly rounding corners 2 and 8.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 1/30/2013

API NO. ASSIGNED: 43013519980000

WELL NAME: Gilbert 14-32-2-3W

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SESW 32 020S 030W

Permit Tech Review: ☒

SURFACE: 0934 FSL 1913 FWL

Engineering Review: ☒

BOTTOM: 0934 FSL 1913 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.26045

LONGITUDE: -110.24972

UTM SURF EASTINGS: 563800.00

NORTHINGS: 4456935.00

FIELD NAME: UNDESIGNATED

LEASE TYPE: 4 - Fee

LEASE NUMBER: Patented

PROPOSED PRODUCING FORMATION(S): GREEN RIVER(LWR)-WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE/FEE - B001834☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 139-90

Effective Date: 5/9/2012

Siting: 4 Prod LGRRV-WSTC Wells

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
10 - Cement Ground Water - hmacdonald
25 - Surface Casing - hmacdonald

RECEIVED: April 09, 2013



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Gilbert 14-32-2-3W
API Well Number: 43013519980000
Lease Number: Patented
Surface Owner: FEE (PRIVATE)
Approval Date: 4/9/2013

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-90. The expected producing formation or pool is the GREEN RIVER(LWR)-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

The 7" casing string cement shall be brought back to $\pm 2000'$ to isolate base of moderately saline ground water.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
 - contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:



For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Patented			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000, Denver, CO, 80202		8. WELL NAME and NUMBER: Gilbert 14-32-2-3W			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0934 FSL 1913 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 02.0S Range: 03.0W Meridian: U		9. API NUMBER: 43013519980000			
PHONE NUMBER: 303 382-4443 Ext		9. FIELD and POOL or WILDCAT: UNDESIGNATED			
COUNTY: DUCHESNE		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/30/2015 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This sundry is being submitted to request an extension to this APD that expires 4/9/2015.					
<div style="color: red; font-weight: bold;"> Approved by the UTAH Division of Oil, Gas and Mining </div> <div style="color: red; font-weight: bold;"> Date: _____ By: </div>					
NAME (PLEASE PRINT) Melissa Luke		PHONE NUMBER 303 323-9769			
SIGNATURE N/A		TITLE Regulatory Technician			
DATE 4/6/2015					



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013519980000

API: 43013519980000

Well Name: Gilbert 14-32-2-3W

Location: 0934 FSL 1913 FWL QTR SESW SEC 32 TWP 020S RNG 030W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 4/9/2013

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Melissa Luke

Date: 4/6/2015

Title: Regulatory Technician Representing: NEWFIELD PRODUCTION COMPANY



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

April 21, 2016

Newfield Production Company
Rt 3 Box 3630
Myton, UT 84052

Re: APD Rescinded – Gilbert 14-32-2-3W, Sec. 32, T. 2S, R. 3W
Duchesne County, Utah API No. 43-013-51998


Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on April 9, 2013. On March 3, 2014 and April 7, 2015 the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective April 21, 2016.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
Brad Hill, Technical Service Manager

